



Walls are lettered **A** through **I** and pertain to the interior of the dispatch area.

- Walls **A**, **B**, and **C** are to be stripped of sheetrock to the studs and replaced with sheetrock, taped, sanded, primed and painted.
 - Wall **A**, fire panel will need to be reinstalled by alarm company and electrician. Timming will need to be coordinated.
- Wall **F**, stripped of sheetrock to the studs and replaced with ½ plywood, sheetrock, taped, sanded, primed and painted.
- Walls **G**, **H**, **I** are Kevlar walls. The integrity of these walls must not be compromised. Wallpaper is to be removed, sanded, primed and painted.
- Wall **B**, the window in between dispatch and records is to be removed and replaced with like studs. Backings will need to be installed for hanging cabinets.
- Kitchen, contractor will be provided with samples for cabinets and style of sink.
 - Remove and dispose of all cabinets
 - Replace sink with under surface sink